

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18390/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Construction of Missing covering Slab in Chamundeswari Layout and Nanjappa Layout in ward no 10 (Doddabommasandra), Vidyanarayapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				K V SUBBA REDDY		
				In Figures		In Words
1	259.2	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	50.0	12960.00	Rupees Fifty Only
2	38.88	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	194400.00	Rupees Five Thousand Only
3	972	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	600.0	583200.00	Rupees Six Hundred Only
4	5400	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	30.66	165564.00	Rupees Thirty and Sixty Six Paise Only
5	972	Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work	Sqm	920.0	894240.00	Rupees Nine Hundred Twenty Only
6	259.2	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	100.0	25920.00	Rupees One Hundred Only
					1876284.00	

K.V. Subba Reddy
Signature of the Contractor

H.V. Y. [Signature]
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
26/2/16